


KHFE, KHFH, KHFP- HORIZONTAL FAN COIL

EXTERNAL FEATURE SPACE REQUIREMENTS MODEL HORIZONTAL FCE

JOB NAME _____
 ENGINEER _____
 CONTRACTOR _____
 TAG _____

SUBMITTAL SHEET



VA. PKG. SIZE	2-WAY VALVE PKG. CODES			3-WAY VALVE PKG. CODES			
	24	25	29	36	37	41, 53	50
1/2"	15-1/2 [394]	19-7/8 [432]	17 [432]	13-1/4 [336]	17-3/4 [451]	15 [381]	13-1/8 [333]
3/4"	12 [304]	20-3/4 [527]	18-1/4 [463]	14-1/4 [362]	18-7/8 [479]	16-5/8 [397]	14-1/4 [362]

NOTES:

- ALL CHILLED WATER PIPING THAT PROJECTS BEYOND THE CONDENSATE PAN OR OPTIONAL AUXILIARY DRIP PAN MUST BE FIELD INSULATED BY OTHERS
- AUXILIARY DRIP PAN SHOWN ABOVE IS OPTIONAL, AND IS MOUNTED ON THE OUTLET END OF THE DRAIN PAN
- DRAIN PAN IS INSTALLED WITH OUTLET TUBE(S) ON COOLING COIL CONNECTION END OF COIL ON 4-PIPE UNITS (OPTIONAL OPPOSITE END CONNECTION)
- DIMENSIONS SHOWN ON THIS DRAWING APPLY TO STANDARD CW AND HW VALVE PACKAGES
- REFER TO THE PIPING PACKAGE CATALOG FOR VALVE PACKAGE CODE DETAILS
- CONTACT FACTORY FOR DETAILS ON VALVE PACKAGES USING NON-STANDARD OR CUSTOMER FURNISHED COMPONENTS
- SOME VALVE PACKAGE APPURTENANCES MAY EXTEND SLIGHTLY ABOVE TOP OF UNIT
- DIMENSION "L" IS +/-1" [25MM] DUE TO MULTIPLE SOURCE COMPONENT DIMENSIONAL VARIATIONS.
- DIMENSIONS ABOVE SHOULD BE USED TO APPROXIMATE SPACE REQUIREMENTS ONLY AND SHOULD NOT BE USED FOR PIPING "ROUGH IN" PURPOSES
- UNIONS AND/OR ADAPTER COUPLINGS ADD UP TO 1" [25MM] TO DIMENSION "L"
- VALVE PACKAGES WITH OPTIONAL STRAINER WILL INTERFERE WITH THE OPTIONAL AUXILIARY DRIP PAN
- STRAINER CLEANOUT VALVE MAY EXTEND BELOW THE BOTTOM OF THE UNIT SLIGHTLY
- PROVIDE SUFFICIENT CLEARANCE TO ACCESS ELECTRICAL COMPONENTS AND COMPLY WITH ALL APPLICABLE CODES AND ORDINANCES
- STANDARD SIDE MOUNTED CONTROL ENCLOSURE IS REPLACED BY THE BOTTOM HINGED CONTROL ENCLOSURE ON UNITS WITH OPTIONAL DOOR INTERLOCKING DISCONNECT SWITCH

Revision Date:

04/15

Form:

FCS01-KHF01

Replaces:

NEW