


| JOB NAME | |
|------------|--|
| ENGINEER | |
| CONTRACTOR | |
| TAG | |

SUBMITTAL SHEET



NDTES:

- 1. ALL RISERS ARE FACTORY TESTED, AND GUARANTEED TO BE LEAK FREE AT TIME OF SHIPMENT.
- 2. RISER INFORMATION SHOWN SHALL REFLECT MATCHING UNIT IDENTIFICATION LABELS.
- 3. KVIS, SLAVE UNITS WILL HAVE MIRROR IMAGE DRIENTATION AND WILL B E LABELED IN UNITS.
- 4. CONDENSATE P-TRAP/HOSE CLAMPS SHIPS INSTALLED IN UNIT FOR FIELD CONNECTIONS TO DRAIN RISER. 5. ALL RISERS AND VALVES ARE SHIPPED WITH PROTECTIVE CAPS. THESE CAPS SHOULD REMAIN IN PLACE
- 5. ALL RISERS AND VALVES ARE SHIPPED WITH PROTECTIVE CAPS, THESE CAPS SHOULD REMAIN IN PLACE UNTIL INSTALLATION OF THE UNIT. DO NOT ALLOW THESE CAPS TO FALL INTO THE UNIT DRAIN PAN AT TIME OF REMOVAL.

Revision Date: 04/15 Form: FCS05-KVPE/KVPP01 Replaces: NEW